

NHC Judicial Building - Furniture Replacement Addendum 1

September 28, 2020

To: All Plan Holders

From: John R Sawyer, AIA



General Items

Specification Items

Drawing Items

Clarifications

- 1) The price sheet included in the bid document has been revised and is enclosed. Changes are highlighted in green.
- 2) All hardware and connectors required for complete workstations shall be included in the proposal.
- 3) Drawing 2:
 - a) The customer service area desks are casework provided by others.
 - b) 4 stools and 1 task chair are to be provided as shown in the customer service area.
 - c) Desks shown along the wall are to be freestanding with O-legs.
- 4) Drawing 3:
 - a) A 42"x24" worksurface is being added to the product breakdown sheet.
 - b) The workstations at the bottom are freestanding and are to be standing height.

Approved Substitutions

The following have been reviewed and accepted:

- 1) None.

End of Addendum 1

ITEM DESCRIPTION	QUANTITY	UNIT COST	EXTENDED COST	ITEM SUMMARY
CUBICLE PANEL				
OPS 2	WIDTH - 24" DEPTH - 2 1/8" HEIGHT - 42"	27		MFG. OPEN PLAN SYSTEMS. OPS 2. SLOTS ALLOW HANGING WORKSURFACES AND HANG-ON UNITS, IN 1" INCREMENTS. POWER AND DATA RACEWAY BASE AND POWER POLE. ADJUSTABLE LEVELING GLIDES.TACKABLE PANELS. STEEL STRUCTURE.
	WIDTH - 36" DEPTH - 2 1/8" HEIGHT - 42"	12		
	WIDTH - 48" DEPTH - 2 1/8" HEIGHT - 42"	12		
WORKSURFACE				
OPS 2	WIDTH - 72" DEPTH - 24"	32		LAMINATE ON 1-1/8" SOLID CORE HIGH PERFORMANCE PARTICLEBOARD. 1 GROMMET PER WORKSURFACE. WORK SURFACE SUPPORTS AS NEEDED.
	WIDTH - 42" DEPTH - 24"	1		
	WIDTH - 48" DEPTH - 24"	24		
	WIDTH - 54" DEPTH - 24"	1		
	WIDTH - 60" DEPTH - 24"	3		
MOBILE PEDESTAL				
OPS 2	WIDTH - 15" DEPTH - 22 7/8" HEIGHT - 22"	28		1 BOX / 1 FILE MOBILE METAL STORAGE UNIT. INNER-FRAME STEEL CONSTRUCTION FULLY ENCLOSED BASE. ALL WELDED CASE CONSTRUCTION. SEAT CUSHION TOP. 4 CASTORS FOR CARPET FLOORING. DRAWER LOCK.
SUPPORT PEDESTAL				
OPS 2	WIDTH - 15" DEPTH - 22 7/8" HEIGHT - 28"	21		2 BOX / 1 FILE FREESTANDING METAL STORAGE UNIT. INNER FRAME STEEL CONSTRUCTION, FULLY ENCLOSED BASE. ALL-WELDED CASE CONSTRUCTION.
O-LEG SUPPORT				
OPS 2	DEPTH - 24" HEIGHT - 28 1/2"	24		STEEL FRAME CONSTRUCTION. ALL FASTENERS CONCEALED, ADJUSTABLE LEVELING GLIDES.
TOP SHELF				
CUSTOM	WIDTH - 72" DEPTH - 16" HEIGHT - 1"	6		LAMINATE SHELF MOUNTED TO CUBICLE PANELS. STEEL SUPPORT ARM BRACKET SECURE SHELF TO PANELS. BRACKETS TO BE COMPATIBLE WITH FURNITURE SYSTEM.
TASK CHAIR				
LIVELLO HIGH BACK	360° SWIVEL SEATING HEIGHT	30		SEAT GLIDE, BUILT IN LUMBAR MID-BACK SUPPORT ADJUSTABLE ARMS. GRADE 1 STAIN RESISTANT FABRIC UPHOLSTERY. WARRANTY MINIMUM - 300 LBS. EXTENDED HEIGHT WITH FOOT REST REQUIRED AT SERVICE COUNTER LOCATIONS.
	360° SWIVEL STOOL HEIGHT	4		
PRIVATE OFFICE DESK				
DESK OPS K SERIES	WIDTH - 71" DEPTH - 30" HEIGHT - 29"	3		L SHAPED DESK. RECESSED MODESTY PANEL. 2 STORAGE PEDESTALS. CENTER DRAWER. OVERHEAD STORAGE CABINET WITH FOUR DOORS.
RETURN OPS K SERIES	WIDTH - 42" DEPTH - 24" HEIGHT - 29"	3		
TOTAL BID AMOUNT				